

Municipal Code Excerpts and Erosion Control Guides for Residential Storm Water Permitting

Section 38.12.420.1 “Mandatory Permits. Any person proposing a development or project which involves land development, land disturbing, or other activities as define in this title, shall obtain a Storm Water management permit before initiating those activities.”

Section 38.14.430 “**Construction Activities**

1.Site Dewatering. Water pumped from the site shall be treated by temporary sedimentation basins, grit chambers, sand filters, up flow chambers, hydro-cyclones, soil concentrators or other appropriate controls as deemed necessary. Water may not be discharged in a manner that causes erosion, sedimentation, or flooding on the site; the receiving channels; or any wetland.

2.Waste and Material Disposal. All waste materials (including garbage, debris, cleaning wastes, wastewater, toxic materials, or hazardous materials) shall be properly disposed of off-site and not allowed to be carried by runoff or wind.

3. Tracking Management. At the end of each work day any material placed on a public or private road shall be removed (not by flushing) to prevent sediment tracking.

4. Water Quality Protection. The construction contractor shall be required to control oil and fuel spills, and the discharge of any chemicals to prevent such spills or discharges from entering any water course, sump, sewer system, water body, or wetland.

5. Site Erosion and Sedimentation Control. Construction operations must include erosion and sedimentation control measures meeting accepted design criteria, standards and specifications. (Ord. No. 1282 § 2)”

Section 38.14.620 “**Costs of Damage**

Any person violating any of the provisions of this title or who initiates an activity which causes deposit, obstruction, or damage or other impairment to the City’s storm water management system is liable to the City for any expense, loss, or damage caused by the violation or the discharge. The City may bill the person violating this title the costs for any cleaning, repair or replacement work caused by the violation of storm water discharge. (Ord. No. 1282 § 2)”

http://www.ndhealth.gov/WQ/Storm/Construction/Homebuilder_brochure2007.pdf

http://www.ndhealth.gov/WQ/Storm/Construction/Homeowner_brochure2007.pdf

http://www.ndhealth.gov/WQ/Storm/Construction/Basic_Requirements2007.pdf